BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Construcions of RCC Drain Opp to Anjaneya Temple Abbigere Village Shettyhalli Sub Division in Ward No.12,

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling size stone masonry in clay mortar /lime mortar/cement mortar and stacking the size stone within a radius of 50m and removing the Debris to a distance upto 200m. complete as per specifications.	Cum	62.64	130.68	Rupees One Hundred Thirty and Sixty Eight Paise Only
2	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m. after breaking of clods complete as per specification.	Cum	700.02	144.72	Rupees One Hundred Forty Four and Seventy Two Paise Only
3	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	70.83	4012.20	Rupees Four Thousand Twelve and Twenty Paise Only
4	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs,with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and Ground Floor level for roof slabs, staircase, lintels retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	283.81	5047.92	Rupees Five Thousand Forty Seven and Ninety Two Paise Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtls	177.28	6382.80	Rupees Six Thousand Three Hundred Eighty Two and Eighty Paise Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Signature of the Contractor

Executive Engineer

6	Providing and removing centering, shuttering, strutting, propping etc., and removal of from work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	1749.60	555.12	Rupees Five Hundred Fifty Five and Twelve Paise Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading.	Cum	700.02	100.35	Rupees One Hundred and Thirty Five Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,